



**Do you have an Upcoming FDNY Test?**  
**Help avoid violations by following the checklist below.**

These are the most common reasons your building will fail if not addressed prior to your **FDNY 5 Year Hydrostatic Test & Residential Flow Test:**



**1** Fire extinguishers are properly mounted, and tags are up to date.



**2** Stairways are clear of all storage.



**3** Stairway doors are self-closing.



**4** Emergency lights are properly working.



**5** All electrical boxes are properly covered.



**6** Fire safety plan hanging in lobby (residential buildings).



**7** Standpipe fire hose is properly racked or rolled in cabinets.



**8** All exits are clear from obstructions such as boxes or garbage.



**9** All storage is removed from electrical rooms.



**10** All mains, risers, and cross connection piping must be painted red on standpipe & sprinkler systems.



**11** All control valve handles must be painted: green for sprinkler – red for standpipe – yellow for combination.

**12** Items hanging from sprinkler piping (even wires) is prohibited.

**13** All storage must be at least 18 inches below all sprinkler heads.

**14** Proper signage on all valves, FDC's, & doors, Compactor rooms must have a sketch of the system hanging behind a glass frame.

**15** All monthly records are up to date.

**16** All control valves are chain and locked or electronically monitored.

**17** All Shrubs and Trees must be cleared 3' around all FDC's (Fire Department Connections)

**18** If your building has scaffolding in front a red light must be provided in front of all FDC's (Fire Department Connections.